

**REQUEST FOR PROPOSALS:**  
**Development of 351 Stephen Street:**



**March 11<sup>th</sup>, 2024**

---

**RFP**  
**DEVELOPMENT OF 351 STEPHEN STREET – REQUEST FOR PROPOSALS**

March 2024

**Part 1 Invitation to Bid**

**1.1 Outline of Offering**

- .1 City of Morden owned downtown property to be sold for private ownership and development.
- .2 The City of Morden will award a 12-month option to purchase for 351 Stephen Street to the successful proponent.
- .3 The site was formerly developed as the provincial land titles building on the north side of Stephen Street with the legal description of 20, 21-27-863 MLTO.

**1.2 Submission Requirements**

- .1 3 paper copies and 1 digital copy [PDF] to be **received by 4:30 April 23rd, 2024** at the Morden Civic Centre [100-195 Stephen Street, Morden MB, R6M 1V3, c/o City Manager]
- .2 Proposal to be addressed to City Manager and clearly marked “351 Stephen Street Development – RFP”
- .3 Proposal must be complete, must be accompanied by a signed letter from a representative of the proponent, and must include proponent contact information; incomplete proposals, proposals submitted without a signed letter, and/or proposals submitted without proponent contact information will not be accepted
- .4 If applicable, include disclaimer concerning use of proprietary information

**1.3 Contact for Enquiries**

Enquiries can be submitted in writing to Jason Dyck through email:  
[Jdyck@mymorden.ca](mailto:Jdyck@mymorden.ca)

- .1 Responses to all enquiries will be included in future addenda.
- .2 Should questions be submitted prior to the proposal due date, all answers will be provided in writing and questions/answers will be shared with anyone party who has requested a copy of the RFP

**Part 2      Background**

**2.1      Location & Site Information**

- .1      The property is located at the northwest corner of the intersection of Stephen Street and 8<sup>th</sup> Street.
- .2      Address:                      351 STEPHEN STREET  
            Legal Description:      20, 21-27-863  
            Lot:                              20, 21  
            Block:                        27  
            Plan:                          863
- .3      The property is approximately 52.7 feet [16.1 m] wide and 125.4 feet [38.2 m] deep = 0.15 acres [0.06 hectares].
- .4      The building footprint is approximately 3,500 square feet, not including the second floor and basement. Exact square footage of the interior is unknown.

**2.2      Buildings & Improvements**

- .1      Schedules for the RFP which detail the status of the building include:
  - .1      Floor Plan
  - .2      Building Statement of Significance
  - .3      Building Condition Report.
    - .1      NOTE: report completed in early 2000s and work has been done since. Site visits encouraged.
  - .4      Haz Mat Report
  - .5      Roofing Report
  - .6      Sewer Line Report

**2.3      Development Plan Designation & Zoning District**

- .1      The property is located within the “Urban Downtown Area” designation under the MSTW Planning District Development Plan which emphasizes:
  - .1      Developments that preserves or compliments the architectural and urban design heritage of downtown buildings.
  - .2      Mixed use developments which may include a combination of commercial and/or multi-family housing

- .2 The property is zoned “CC – Commercial Central” district under the Morden Zoning By-Law 08-2017
- .3 Building does not have formal heritage status, though the Building Statement of Significance identifies numerous design elements which are required to be maintained or enhanced.

## **2.4 Infrastructure**

- .1 The property is serviced by piped water and sewer lines
- .2 The property is accessed via an undivided two-way road, with on-street parking
- .3 Hazardous materials report appended to this RFP.

## **2.5 Bidder’s Due Diligence**

- .1 **A site visit will be arranged on March 18<sup>th</sup> from 1-3 pm** for proponents to see the site firsthand. Proponents to meet at the entrance to 351 Stephen St.
- .2 The documentation contained in this RFP as Schedules is not to be considered comprehensive as work has taken place since they were produced and prospective proponents are encouraged to undertake their own review and analysis concerning physical conditions, environmental conditions, zoning requirements, title instruments, and applicable permits and approval procedures

## **2.6 Development Requirements**

- .1 Development to be consistent with the development plan’s intent for Urban Downtown Areas and Zoning By-Law 08-2017.
- .2 Development to be initiated within 12 months of award and substantially complete no later than one year from the exercise of the option to purchase.
- .3 Heritage
  - .1 Proposals shall address the degree to which proposed development maintains or enhances the historical significance of the building further described in the Building Statement of Significance and including, but not limited to:
    - .1 Maintaining or enhancing those exterior architectural features identified in the as both “Important” and “Minor” qualities in the report.
    - .2 Existing windows may be replaced with energy efficient sealed units.
    - .3 Original rough openings for windows/doors, including stone sills and masonry arches, must remain.

.4 Interior Qualities deemed important are encouraged to remain wherever practical.

.4 Development Permit

- .1 Due to the limited capacity of wastewater infrastructure, a development permit will be issued subject to the condition that water usage from the proposed redevelopment shall not exceed the historic water usage of the property as Land Titles Office significantly and subject to meeting other applicable municipal bylaws and provincial statutes. The water usage restriction condition will be removed upon completion of a new wastewater treatment system.
- .2 For mixed-use proposals, development permits for the portion of the development which includes new residential development will only be issued upon completion of new wastewater infrastructure.

**2.7 Proposal Evaluation Criteria**

- .1 Demonstrates advancement of development plan principles for this Urban Downtown Area as well as the following —pedestrian-friendly, vibrant community; preserves heritage, innovative & fun, prioritizing mixed-use developments that optimize the use of land and municipal services
- .2 Offer amount for the lot purchase, estimated total construction cost, estimated post-development tax generation.
- .3 Demonstrates proponent’s expertise & experience developing similar properties.

**2.8 Detailed Submission Requirements**

- .1 Identify the proponent or development team, with contact information.
- .2 Provide background information concerning the proponent or development team [i.e. property development experience, representative projects, local projects]
- .3 Provide detailed development concept, including dimensioned floor plans.
- .4 Provide description of how the proposal satisfies development plan principles and downtown and heritage design objectives.
- .5 Include offer price for the property as well as a proposed amount for a non-refundable deposit to secure the option. This will form the basis for a forthcoming option to purchase agreement and subsequent offer to purchase agreement. All conditions subject to approval by Council.

**2.9 Selection Process & Execution of Purchase Agreement**

- .1 Review of complete proposals
- .2 Selected proposal presented to City Council

- .3 12-month option awarded to successful proponent.
- .4 Execution of agreement
- .5 Exercise of option and transfer of title upon review of detailed development design by City Engineering Department.

**2.10 Qualifiers**

- .1 Morden City Council members and City of Morden staff members are ineligible
- .2 Successful proposals will not constitute a contract with the City of Morden.
- .3 Purchaser is solely responsible for obtaining any approvals required for development and paying applicable levies.
- .4 Proposals shall be valid for a period of no less than 60 days from the close of the RFP.
- .5 City of Morden reserves the right to reject any and all proposals for any reason at its sole discretion, to negotiate the terms and conditions of the eventual contract with the purchaser, and to impose additional restrictions if deemed necessary
- .6 Contents of this package are for information purposes only and the representations made herein, though thought to be accurate, are without warranty; proponents are advised to rely exclusively on their own investigations and analyses
- .7 City of Morden will honour confidentially requests to the extent possible; if information contained in the proposal is proprietary, please mark as such

**2.11 Schedules**

- A. Site map
- B. Floor Plan
- C. Building Statement of Significance
- D. Building Condition Report
- E. Haz Mat Report
- F. Roofing Report
- G. Sewer Line Report
- H. Status of title

**END OF SECTION**

**SCHEDULE A**

**SITE MAP**

Address: 351 STEPHEN STREET  
 Roll ID: 100700  
 Legal Description: 20, 21-27-863  
 Lot: 20, 21  
 Block: 27  
 Plan: 863





**City of Morden**  
100-195 Stephen Street  
Morden, Manitoba, R6M 1V3  
Telephone: 204-822-4434 | Fax: 204-822-6494

---

**SCHEDULE B**

**FLOOR PLAN**





Manitoba  
 1000-10th Avenue, Winnipeg, Manitoba R2P 1K1

Item	Description	Quantity	Unit	Value
1	...	...	...	...
2	...	...	...	...
3	...	...	...	...
4	...	...	...	...
5	...	...	...	...
6	...	...	...	...
7	...	...	...	...
8	...	...	...	...
9	...	...	...	...
10	...	...	...	...
11	...	...	...	...
12	...	...	...	...
13	...	...	...	...
14	...	...	...	...
15	...	...	...	...
16	...	...	...	...
17	...	...	...	...
18	...	...	...	...
19	...	...	...	...
20	...	...	...	...
21	...	...	...	...
22	...	...	...	...
23	...	...	...	...
24	...	...	...	...
25	...	...	...	...
26	...	...	...	...
27	...	...	...	...
28	...	...	...	...
29	...	...	...	...
30	...	...	...	...
31	...	...	...	...
32	...	...	...	...
33	...	...	...	...
34	...	...	...	...
35	...	...	...	...
36	...	...	...	...
37	...	...	...	...
38	...	...	...	...
39	...	...	...	...
40	...	...	...	...
41	...	...	...	...
42	...	...	...	...
43	...	...	...	...
44	...	...	...	...
45	...	...	...	...
46	...	...	...	...
47	...	...	...	...
48	...	...	...	...
49	...	...	...	...
50	...	...	...	...
51	...	...	...	...
52	...	...	...	...
53	...	...	...	...
54	...	...	...	...
55	...	...	...	...
56	...	...	...	...
57	...	...	...	...
58	...	...	...	...
59	...	...	...	...
60	...	...	...	...
61	...	...	...	...
62	...	...	...	...
63	...	...	...	...
64	...	...	...	...
65	...	...	...	...
66	...	...	...	...
67	...	...	...	...
68	...	...	...	...
69	...	...	...	...
70	...	...	...	...
71	...	...	...	...
72	...	...	...	...
73	...	...	...	...
74	...	...	...	...
75	...	...	...	...
76	...	...	...	...
77	...	...	...	...
78	...	...	...	...
79	...	...	...	...
80	...	...	...	...
81	...	...	...	...
82	...	...	...	...
83	...	...	...	...
84	...	...	...	...
85	...	...	...	...
86	...	...	...	...
87	...	...	...	...
88	...	...	...	...
89	...	...	...	...
90	...	...	...	...
91	...	...	...	...
92	...	...	...	...
93	...	...	...	...
94	...	...	...	...
95	...	...	...	...
96	...	...	...	...
97	...	...	...	...
98	...	...	...	...
99	...	...	...	...
100	...	...	...	...

Manitoba  
 1000-10th Avenue, Winnipeg, Manitoba R2P 1K1

Manitoba  
 1000-10th Avenue, Winnipeg, Manitoba R2P 1K1

Manitoba  
 1000-10th Avenue, Winnipeg, Manitoba R2P 1K1


Manitoba  
 1000-10th Avenue, Winnipeg, Manitoba R2P 1K1

Manitoba  
 1000-10th Avenue, Winnipeg, Manitoba R2P 1K1


Manitoba  
 1000-10th Avenue, Winnipeg, Manitoba R2P 1K1


Manitoba  
 1000-10th Avenue, Winnipeg, Manitoba R2P 1K1

Manitoba  
 1000-10th Avenue, Winnipeg, Manitoba R2P 1K1



**BUILDING #313  
BASEMENT**



 Asbestos Floor Tile

**Mankoba**  
 International  
 Administration Services Division  
 1707 Prince of Wales Drive, Winnipeg, Manitoba R2N 2A1

**Notes:**  
 This drawing shall not be used for construction purposes. It is for informational purposes only. The contractor shall verify the location and extent of asbestos before any construction of work commences. The contractor shall be responsible for any asbestos abatement work required. This drawing shall not be used for any other purpose without the written approval of the client.

**Project Name:** LAND TILES BLDG  
**351 STEPHEN STREET  
 NORTH**

**Project Number:** 100013  
**Drawn By:** Dan Gryniewicz  
**Date:** 2018-08-23

**Scale:** 1:100

**Orientation:** 


**Legend:**  
 FT Asbestos Floor Tile

**Scale:** 1/8" = 1'-0"

**Drawn By:** Dan Gryniewicz  
**Date:** 2018-08-23



**Sheet Number:** A-3.0

BUILDING #313  
FIRST FLOOR



Environmental Liabilities (All Floors):  
All Removed 2009

Environmental Liabilities Removed (All Floors):  
Ceiling Tiles - 2000 Sq. Ft.  
Floor Tiles - 1000 Sq. Ft.  
Insulation in Outside Walls - 1710 Sq. Ft.  
Mould - 5886 Sq. Ft.  
PCB Lights - 8  
Asbestos Drywall Compound - 1500 SqFt.

 Asbestos Ceiling Tile  
 Asbestos Floor Tile


No. 1. Revision Date By  
This drawing shall not be used, either prior or subsequent to the completion of the project, without the written consent of the author. The author shall not be held responsible for any errors or omissions in this drawing. The author shall not be held responsible for any errors or omissions in this drawing. The author shall not be held responsible for any errors or omissions in this drawing.

Project Name: Project Number:  
Drawing No.: 2013-01-03  
Drawing Date: 2013-01-03  
Drawing By: (Name) (Signature)



Project Title: LAND TILES BLDG  
351 STEPHEN STREET  
MORRIS  
MORRIS  
PROJECT ROOM 244A-COMPOSITE ENVIRONMENTAL LIABILITIES  
Scale: 1:100  
Date: 10/03/13  
Drawing No.: A-1.0

**BUILDING #313  
SECOND FLOOR**



**FT** Asbestos Floor Tile

No.	Location	Date	By

The client and not the consultant, retains joint responsibility with the consultant for the accuracy and completeness of the information and data provided. The consultant shall not be held responsible for any errors or omissions in the information provided by the client. The consultant shall not be held responsible for any errors or omissions in the information provided by the client. The consultant shall not be held responsible for any errors or omissions in the information provided by the client.

**Project Manager:** Project Leader  
**Designed by:** 2018-04-23  
**Drawn by:** Date: 2018-04-23  
**Scale:**



**Comments:**

**Project Title:** 2ND FLOOR  
**Address:** 2ND FLOOR  
**Address:** 321 STEPHEN STREET  
**Address:** NORDEN

**Client:** 2ND FLOOR  
**Client:** 2ND FLOOR  
**Client:** 2ND FLOOR  
**Client:** 2ND FLOOR

**Client:** 2ND FLOOR  
**Client:** 2ND FLOOR  
**Client:** 2ND FLOOR  
**Client:** 2ND FLOOR

No.	Description	Date	By
3	Drawing updated to reflect current	2015-07-13	AM
4	Initial drawing number	2015-07-13	AM
5	Drawing added to user accounts	2015-07-13	AM

This drawing shall be used for construction only. The contractor shall verify the accuracy of the information shown on this drawing. It is the responsibility of the contractor to verify the accuracy of the information shown on this drawing. It is the responsibility of the contractor to verify the accuracy of the information shown on this drawing. It is the responsibility of the contractor to verify the accuracy of the information shown on this drawing.


Project Manager	Project Leader
Designed by	Reviewed by
Drawn by	Date: 2015-07-13
Notes	Date: 2015-07-13

Project Manager: \_\_\_\_\_  
 Project Leader: \_\_\_\_\_  
 Designed by: \_\_\_\_\_  
 Reviewed by: \_\_\_\_\_  
 Drawn by: \_\_\_\_\_  
 Date: 2015-07-13  
 Notes: \_\_\_\_\_  
 Date: 2015-07-13



Project Title: **LAND TITLES BUILDING**  
**351 STEPHEN STREET**  
 MORDEN  
 Project Title: **BASIS/CHIT**  
 MANTOBA


Scale	1 : 30
ABP Building Number	100313
Drawn Project Number	1 OF 3
Sheet Number	0



Outside Area: 351.21  
 Inside Area: 296.56  
 Wall Area: 64.65


No.	Description	Date	By
1	Issued to be used as a record	2007/07/12	AD
2	Added record number	2011/06/24	CR
3	Issued to be used as a record	2012/04/11	SP

The drawings shall not be used, copied, altered, or otherwise reproduced without the written consent of the architect. The architect shall not be held responsible for any errors or omissions in the drawings. The architect shall not be held responsible for any errors or omissions in the drawings. The architect shall not be held responsible for any errors or omissions in the drawings.

Project Manager: \_\_\_\_\_ Project Leader: \_\_\_\_\_  
 Completed by: \_\_\_\_\_ Prepared by: \_\_\_\_\_  
 Drawn by: \_\_\_\_\_ Date: July 2007  
 North:  Date: (Optional) \_\_\_\_\_  
 Consultant: \_\_\_\_\_

Project Title: **LAND TITLES BUILDING**  
**351 STEPHEN STREET**  
 WOODEN  
 MANITOBA  
 Sheet Title: **FIRST FLOOR**


Scale	1:100
Job Drawing Number	1000313
Optional Project Number	
Job Project Number	2 of 3
Revised	0



Outside Area: 354.98  
 Inside Area: 299.49  
 Wall Area: 55.49


1	Revised to include work	2005-07-13	all
2	Revised to include work	2005-07-13	all
3	Revised to include work	2005-07-13	all

**Notes:**  
 The client shall not be liable for any errors or omissions in this drawing. The contractor shall verify all dimensions and locations of work shown on this drawing. The contractor shall be responsible for any discrepancies between this drawing and the actual site conditions. The contractor shall be responsible for any discrepancies between this drawing and the actual site conditions. The contractor shall be responsible for any discrepancies between this drawing and the actual site conditions.

**Project Manager:** Project Leader  
**Designed by:** Designer  
**Drawn by:** July 2005  
**Check:** Date (00/00/0000)  
**North:**   
**Consultant:**

**Project Title:** LAND TITLES BUILDING  
 361 STEPHEN STREET  
**Sheet Title:** MORDEN  
 MANITOBA  
 SECOND FLOOR PLAN

<b>Scale:</b> 1:100	<b>Drawn:</b> Project Manager
<b>MSD Building Number:</b> 100313	<b>Sheet Number:</b> 3 OF 3
<b>MSD Project Number:</b>	<b>Revision:</b> 0



**Outside Area:** 353.09  
**Inside Area:** 294.79  
**Wall Area:** 58.30

No.	Description	2009-01-15	SP
5	Items noted in the schedule		

The client shall be noted. Value given structure only.  
 The schedule shall include a list of structure and  
 items shown on site.  
 In the event of any items not shown on site,  
 the contractor shall be responsible for providing  
 a list of items not shown on site.  
 The contractor shall be responsible for providing  
 a list of items not shown on site.  
 The contractor shall be responsible for providing  
 a list of items not shown on site.

Project Location  
 Designed by  
 Drawn by  
 Date  
 North

Project Location  
 Designed by  
 Drawn by  
 Date  
 North


Project Location  
 Designed by  
 Drawn by  
 Date  
 North

Project Location  
 Designed by  
 Drawn by  
 Date  
 North

Project Location  
 Designed by  
 Drawn by  
 Date  
 North

Project Location  
 Designed by  
 Drawn by  
 Date  
 North

Scale	1:100
JOB Drawing Number	100313
JOB Project Number	
Sheet Number	



- LEGEND (PS# 300313)
- LAMP POST □
  - SHRUBS / TREES ●
  - WATER MAIN ○
  - TRAFFIC LIGHT □
  - FIRE HYDRANT ●





1998 - 1999

1. Name of the building	2. Address	3. City	4. Province

5. Date of construction	6. Date of renovation


The owner of this building is responsible for the accuracy of the information provided. The Manitoba Building Department is not responsible for the accuracy of the information provided.

Manitoba Building Department  
 1000 - 10th Avenue West  
 Winnipeg, Manitoba R2G 1P1  
 Tel: (204) 986-2222  
 Fax: (204) 986-2223

Project Name: \_\_\_\_\_  
 Address: \_\_\_\_\_  
 City: \_\_\_\_\_  
 Province: \_\_\_\_\_  
 Date: \_\_\_\_\_

Scale: \_\_\_\_\_  
 Drawing No: \_\_\_\_\_  
 Revision: \_\_\_\_\_

Project Name: \_\_\_\_\_  
 Address: \_\_\_\_\_  
 City: \_\_\_\_\_  
 Province: \_\_\_\_\_  
 Date: \_\_\_\_\_



LEGEND (PS# 300313)

30135 (58-021) 50A-1P1 - Land Title Registration - 278.14

- Core Service 9.07
- Penetration 12.12

Outside Area: 354.07  
 Inside Area: 288.33  
 Wall Area: 50.54  
 Usable Area: 278.14



Manitoba  
1975 Highway 95, Winnipeg, Manitoba, R2V 1A1

1	Working Drawing No.	300313
2	Revision	
3	Date	

The drawings and specifications are to be used for the construction of the building shown on the drawings. The drawings and specifications are to be read in conjunction with the contract documents. The drawings and specifications are to be used for the construction of the building shown on the drawings. The drawings and specifications are to be read in conjunction with the contract documents.


Project Name: 300313  
 Project No: 300313  
 Date: 1/1/00

Scale: 1/8" = 1'-0"  
 North Arrow



Project Name: 300313  
 Project No: 300313  
 Date: 1/1/00

300313	300313	300313	300313
300313	300313	300313	300313
300313	300313	300313	300313



**LEGEND (PS#300313)**

300313 Condemned Second Floor - Unusable Area 288.07

Penetration 0.72

Outside Area: 303.09  
 Inside Area: 294.78  
 Wall Area: 58.30

300313 Condemned Second Floor - Unusable Area 288.07

Penetration 0.72

Outside Area: 303.09  
 Inside Area: 294.78  
 Wall Area: 58.30



**City of Morden**  
100-195 Stephen Street  
Morden, Manitoba, R6M 1V3  
Telephone: 204-822-4434 | Fax: 204-822-6494

---

**SCHEDULE C**

**BUILDING STATEMENT OF SIGNIFICANCE**

# 100313 - Morden Land Titles Office

(Site of Potential Municipal Significance)

## Statement of Significance



## Description of Historic Place

The Morden Land Titles Building, a two-storey masonry structure built ca. 1896, occupies a prominent corner lot on the main business street in downtown Morden.

## Heritage Value

### Important Values

- The Morden Land Titles Building has important heritage significance because of its claim as an early, and very good, example of the kind of substantial commercial establishment that once defined Manitoba's main commercial thoroughfares, but which is now becoming more uncommon (with demolitions and community contraction). Erected for the H. Meikle General Store and used as a branch of the Bank of Hamilton, the building originally featured shops and offices and a residence on the upper floors.
- The building also has important heritage significance because of its construction – of coarse ashlar masonry which utilized the readily available and abundant local granitic fieldstone from around Morden. The use of this material is fairly common in Morden (used on a few other commercial buildings and in several large houses), and is the source of considerable local pride. Throughout the province, commercial buildings of stone are prized local landmarks – because of their sturdy construction they have endured and are often one of the last remaining to recall an earlier commercial building type.

### Minor Values

- The building has minor heritage significance because of its present function, as a land titles office. Acquired by the province after 1910 and extensively reworked with a vault room of heavy construction, the building is the second land titles registry in Morden, providing continuous use for more than a century.
- The Morden Land Titles Office also has minor value because it is an element in Morden's Stephen Street historic area, which is defined by a fine collection of historic buildings.

## Character-Defining Elements

### Exterior Qualities

Important external elements that should be respected to ensure that the value of the building's exterior character is conserved include:

- its deep and two-storey L-shaped form, solid stone bearing walls and a flat roofline with a parapet and a pressed tin cornice that runs along the south and east facades
- the exceptional native stone finishes and heavy materials, including the roughly split and squared fieldstone with rough limestone trim, stone quoins, brick chimneys
- the balanced composition of the front (south) facade with a similar pressed tin cornice that wraps around the east elevation at the first floor level
- the numerous openings, including on all elevations mostly segmental arched sash windows with limestone voussoirs and lugsills, the smaller segmental arched windows on the lower level of the side elevations

Minor elements that ought to be respected to ensure that the value of the building's exterior character is conserved include:

- other details and materials, such as the acroteria/cornice ornaments, metal coping and downspouts, etc.

### Interior Qualities

Important elements that should be respected to ensure that the value of the building's interior character is conserved include:

- the deep main floor plan, its front offices divided by heavy vault doors to the rear room; and the small west side offices with a stairwell to the second floor
- finishes and features, such as the dark-stained wainscoting, woodwork and built-in fireplaces in the second floor rooms, hardwood flooring etc.
- the heavy protective materials, including the thick stone walls, solid concrete floor and columns that support the main floor and upper levels, the heavy iron vault door

Minor elements that ought to be respected to ensure that the value of the building's interior character is conserved include:

- the second floor main large rooms leading off a side hallway; the west side small rooms
- the use of high transom windows in the doorways, that carries through from the exterior
- the open basement with fieldstone walls

### Site Qualities

Key elements that define the site character of the Morden Land Titles Building include:

- its location in close proximity to other historic buildings in downtown Morden
- the building's placement, flush to the public sidewalk at northwest 8th Street and Stephen Street



**City of Morden**  
100-195 Stephen Street  
Morden, Manitoba, R6M 1V3  
Telephone: 204-822-4434 | Fax: 204-822-6494

---

**SCHEDULE D**

**BUILDING CONDITION REPORT**

**REPORT TO**  
**MANITOBA GOVERNMENT SERVICES**  
**ACCOMMODATION DEVELOPMENT DIVISION**  
**REGARDING**  
**LAND TITLES BUILDING**  
**MORDEN, MANITOBA**

**Third Party Disclaimer**

This Report has been prepared for Manitoba Government Services, Accommodation Development Services for their own information and may not be used or relied upon by any other person unless that person is specifically named by us in this report as a beneficiary of the Report, in which case the Report may also be used by the additional beneficiary we have named. You agree to maintain the confidentiality of the Report and reasonably protect the Report from distribution to any other person. If you directly or indirectly cause the Report to be distributed to any other person, you agree to indemnify, defend, and hold us harmless if any third party brings a claim against us relating to our inspection or the report.

**INDEX**

**PAGES**

	EXECUTIVE SUMMARY	1 - 3
1.	INTRODUCTION	1
2.	SITE VISIT REPORT	1 - 6
3.	DISCUSSION	6 - 10
4.	CONCLUSIONS	10 - 12

**APPENDICES**

APPENDIX I:           PHOTOGRAPHS



---

**EXECUTIVE SUMMARY**

The writer has reviewed previous reports regarding this building as well as other documentation which was provided to this office prior to the actual site visit. The site visit has been completed and the following report and photographs indicate our findings relative to the present condition.

Essentially over the years we found there are two diametrically opposed views with respect to heritage buildings of this kind. When significant maintenance is delayed and then becomes a significant cost factor, frequently the reaction is to demolish the building. The other to which we subscribe having had considerable experience with heritage buildings and restoration of same, is that specific buildings frequently warrant expenditures to maintain them in service as well as the heritage and historic aspect within the community. In our opinion the Land Titles Building in Morden falls under this second category.

Whilst there is no doubt that significant repair, restoration and upgrading are required due to neglect over many years, essentially we find the building to be structurally adequate if said repairs are undertaken in a proper manner. The exterior face of the entire building requires repointing since previous work was not accomplished in the correct manner and for the most part has delaminated from the stone and concealed mortar. If the building is to be retained, some research needs to be done before repointing is undertaken in order to determine the kind of mortar joints, any specific shape which may have applied, as well as other details relative to the exterior refinishing. As well, whilst the cornice and feature trim appears to be in good condition, this should be investigated in more detail prior to instituting the exterior works.

Unquestionably there has been movement and settlement of the foundation walls which are likewise of field stone. On the basis of what can be seen in the basement, the walls appear typical of buildings of this type. No concrete spread footing was ever provided, but merely an extension of the wall using the stone as the actual footing material. Whether or not concrete had been used in lieu of stone, the soil conditions and other aspects of the location would almost certainly have allowed the settlement which has occurred, both differential and general. From information provided it appears that the most significant settlement has occurred along the east and west walls, which resulted in the main floor, which is of concrete, "dipping" to both east and west. This has now been "corrected" by

**EXECUTIVE SUMMARY (CONTINUED)**

installation of a sub-floor and other interior works which were recently completed. Insofar as the exterior field stone walls themselves are concerned, whilst there are open joints, particularly between the vault and the main two storey building at the front, this like other movement cracks and separations can readily be repointed and potentially reinforced using either carbon fibre, fibreglas or similar rods embedded in the joints to assist in maintaining the position of the stone on both sides of the joint.

The second floor has of course been unheated and unoccupied for a number of years, by my understanding more than 10. Notwithstanding, due to what we believe to be the heat losses from the main floor migrating up into the second floor, the deterioration is far less than one would normally find in an unheated building of this kind. There are some signs of settlement and other such damage in specific areas, but based on this first view of the condition, it appears the majority of the second floor is in relatively good condition from a structural viewpoint, other than where the wall has buckled and tension ties were installed. However that installation has not in our opinion really achieved anything and reconstruction of the wall in those areas is quite feasible and structurally poses no significant problem. The access to and from the second floor is obviously "non-conforming" in terms of fire codes and building code requirements and would require changes as part of any upgrading. At this time we believe the specific settlement problems manifested in the second floor can be resolved should a decision be made to retain the building.

Due to the recent upgrading of the main floor and particularly the vault, there were no signs of significant problems, which again by reading files and talking to staff did not appear to have been overly significant in the first place. We suggest that the movement of the main floor slab down towards the east and west sides is due to the settlement of those perimeter walls. Insofar as the front office space is concerned, this is fully finished and none of the existing structure is open to view, nor were there any signs of building problems.

After reviewing documentation provided and visiting the building, we disagree with comments which have been made in the past regarding the need to demolish this building. We suggest it is of a unique nature, being constructed of field stone which material has only local use in and around the Morden area and therefore constitutes a specific aspect of a heritage building. Having been

---

**EXECUTIVE SUMMARY (CONTINUED)**

associated with numerous heritage buildings we believe this building should be restored fully and such changes made as are necessary to conform to the current Building Code requirements. At this stage it is not possible to provide even a preliminary budget since the Province's potential use, its upgrading standards and other aspects of the work including HVAC systems are unknown. If a management decision is made to seriously consider restoration and maintaining this building, then we suggest the entire interior second floor be stripped back to bare stone walls to allow a better review of the stone condition and particularly the bowing of the wall at the northwest corner of the west annex. Finally, therefore, in our opinion whilst some repairs are required which could be designated as structural, we do not find this building to be structurally inadequate, dangerous or beyond reasonable repair and upgrading should there be a will and decision to maintain the facility.

**REPORT TO  
MANITOBA GOVERNMENT SERVICES  
ACCOMMODATION DEVELOPMENT DIVISION  
REGARDING  
LAND TITLES BUILDING  
MORDEN, MANITOBA**

**1. INTRODUCTION**

As a precursor to undertaking the first site visit, we were provided with copies of some past correspondence regarding the subject building, together with an outline specification and quotation for stone repointing which was solicited in 1997. Also, as part of our preliminary briefing we were advised that the second floor above the Land Titles Office space had been closed for several years due to "bowing" of the stone walls at the second floor level. We were also advised that several "tension ties" had been installed in an effort to stabilize the condition.

The writer attended at the premises on Wednesday morning, August 22<sup>nd</sup>, 2001. At that time I met with Mr. Vic Rempel who thereafter acted as "guide" to the various areas of the building and was able to provide certain background information on past events.

**2. SITE VISIT REPORT**

- .1 The building is located at the northwest corner of Stephen and 7<sup>th</sup> streets (photo 1) with the south and east elevations fronting onto the town sidewalk. The building is an example of the use of field stone which material is primarily limited to the Morden area of Manitoba. The stone wall construction commences at the footings in both basement areas and extends up through the building as bearing wall systems to the roof line. Without doing any additional wall dismantling, bearing in mind certain wall areas could be seen in both sections of the building, it appears that the corridor bearing walls in the two storey section containing the Land Titles Office are of field stone.
- .2 The vault floor framing is of concrete construction and consists of large poured in place columns and beams with a concrete slab spanning between the east and west stone walls with a centre concrete beam at both the main and second floor levels; the roof framing system is of wood joist construction.

2. SITE VISIT REPORT (CONTINUED)

The main floor framing in the Land Titles area consists of wood joists and the second floor appeared to be a concrete slab spanning between the bearing wall systems. This slab has been finished at the second floor by installing wood sleepers with the space between these sleepers above the concrete filled with ashes and a tongued and grooved Douglas Fir floor board system installed over the sleepers as the flooring.

- .3 The building review commenced with an exterior "walk around" to consider the condition of the stone and mortar joints. The stone itself appears to be in excellent condition, but the mortar joints are in very poor condition having been repointed at some time with a method and material which was inappropriate. The mortar has almost entirely delaminated from both the stone and the remaining mortar joint that was left between the stones behind the repointing. The original front section of the building occupied by Land Titles appears to be in relatively good condition, with significantly less sign of movement than the rear portion encompassing the vault and the north and northwest corners of the office section itself.

A significant separation crack exists in the east wall between the two storey building and the vault (photos 3 & 5) where differential movement between the two portions has occurred. Once again the infill mortar used at some time to fill the gaps was incorrectly done, essentially this joint separation is open to weather penetration (photo 4).

- .4 Moving along the east wall past the vault separation to the northeast corner, I found that the north face wall at the northeast corner is likewise exhibiting considerable signs of movement, and generally in poor condition, though not structurally inhibiting the performance of the building (photos 7 & 8). The north wall of the "vault" exhibits a variety of mortar degeneration and settlement movement which is particularly evident at the two corners. At the northwest corner of the "vault", it appears that past settlement has occurred and attempts have been made to re-mortar the joints and seal the wall. This movement can be seen in photograph 11 showing the northwest corner, west side.

2. SITE VISIT REPORT (CONTINUED)

- .5 At the northwest corner the fire escape to the second floor requires attention, since the anchorage into the stone is suffering from the general wall movement (photo 9). As well, there are separations in the lower section of the north face (photo 10).
- .6 Moving along the west wall of the vault area, the wall itself is in relatively good condition other than once again for the mortar degeneration and need for repointing.
- .7 The north face of the two storey office section at the west side of the lot is in extremely poor condition (photo 12) and attempts appear to have been made to deal with the stone movement and mortar joint degeneration by applying a cement parge coat. However, not surprisingly this has delaminated and is not performing any useful function at the present time, nor does it appear to have done so for some years past. In the northwest corner of this section (photos 13 & 14) the wall again is showing signs of degeneration due to settlement and mortar joint damage.
- .8 The west face of the office section was difficult to view due to the proximity of the adjacent building on the next lot. A steel channel can be seen where the tension tie rods at the second floor pass through the wall and were bolted through this channel which was obviously intended to act as a "spreader" and hold the wall in position. The remainder of that wall again has suffered some minor settlement, but on this first review does not appear to be suffering any significant structural damage.
- .9 The front elevation of the building (photo 32) portrays the primary architectural treatment of the original building. The sheet metal cornice at the second floor and roof is very decorative and appears to be in good condition, subject to a more detailed examination at some time in the future. This is quite ornate for cornices of this type (photo 2) and has been well maintained. Unlike the other wall areas, the south face appears to be in better condition with fewer signs of movement apart from the need for mortar joint repointing.

**2. SITE VISIT REPORT (CONTINUED)**

- .10 After completing the exterior review I moved to the inside and commenced the review at the second floor which has been closed down and unheated for several years. The plaster and wood lath finish to the walls and ceilings are obviously showing deterioration as a consequence of the absence of heat. In addition, a variety of movement cracks can be seen (photos 19 & 20). However, with one or two notable exceptions the walls appear to be relatively plumb and straight when looking along the corridor and elsewhere, other than the specific area affected by the wall buckling and tension tie installation.
- .11 One particular doorway (photo 21) exhibits significant movement and the second floor in this area obviously has moved and has a "hump" in it. However, walking through the majority of the second floor we found this to be relatively level with only minor signs of movement. There are other specific locations, particularly in the area adjacent to the tension ties at the northwest corner of this area of the building which are likewise out of level, but any effect in the main floor below could not be seen due to the ceiling finishes in the office area itself.
- .12 The rod tension ties (photos 15 & 16) which were installed between the west wall at the second floor and the corridor wall appear to have pulled the corridor wall in, or both walls have moved laterally together. It was not possible under the present conditions with the walls basically finished, to determine which has in fact occurred. However, the lateral movement is not considered to be significant and further discussion on this is offered in the next section of this report.
- .13 The floor construction referred to in item 2.2 is not unique (photo 18). The use of a steepened system with the spaces infill ed with ashes as sound insulation was quite common in the absence of insulation materials such as are now available. The Hudson's Bay store in Winnipeg is constructed with this system.
- .14 Moving back down to the main floor level and the finished office space, there was virtually nothing to be seen due to the finishing and modern decor. The only signs of movement at this time in the general office area were to the wall adjacent to the basement stairs by the vault (photo 22) and the corner office occupied by Mr. Lille; here again the drywall separation is minor and not of any structural significance.

**2. SITE VISIT REPORT (CONTINUED)**

- .15 Moving into the vault itself and being aware that this has recently been upgraded, we found few signs of movement except at the north end and the last span of the second floor support beam and column (photos 23 & 24). This has previously been referred to by Mr. Malus in his reports. At this time I believe there may actually be some "parging" over the original concrete, since the diagonal cracking is unusual for a concrete structure of this kind, notwithstanding the fact that it appears to be related to settlement of the north wall. Elsewhere in the vault area there are two minor ceiling-wall separations, one being in the east wall adjacent to the divider between this section and the main office building where there is the significant separation on the exterior face (the rear wall of Mr. Lille's office). The other is on the west wall almost opposite and again close to the area of the basement stairs.
- .16 Moving into the smaller basement under the front office section I found the stone walls to be exhibiting the typical loss of mortar due to moisture penetration and the effect on soft lime mortar that was used in those days. Some repointing has been done, but been done inadequately since the mortar has fallen out of the wall, or is delaminated. Both here and under the vault I found the basement wall mortar joints have been leaching sand into the basement as the mortar joints deteriorated (photos 30 & 31). Again, this is not an unusual occurrence for rubblestone walls, or in this case the field stone wall. Notwithstanding the mortar degeneration and the fact that the wall appears to have settled, there is no significant stone separation or structural damage from differential movement along the length of these walls.
- .17 In viewing the concrete beams under the vault main floor I found some cracking (photos 25 & 26) in the same general area as that which can be seen at the second floor where the columns and beams extend up through the vault area. Again, these cracks are minimal and are discussed later in this report.
- .18 At only one location in the vault basement did we find any significant concrete deterioration (photo 28). At this time we cannot comment as to why this one location has suffered this badly, but do speculate in the next section of the report.



2. SITE VISIT REPORT (CONTINUED)

.19 Typical of old basements, the basement floor itself is in poor condition, but since this is unused space, has no relevance to the building structure. However, the migration of moisture into the basements both through the walls and up through the floor, does have an impact which again is discussed later.

3. DISCUSSION

.1 As was apparent from the tender which was solicited in 1997 for repointing of the exterior face of the stone walls, the mortar joints are in extremely poor condition. However, we are not aware whether or not deterioration has increased since the time the specification and sketch was prepared, but at this time based on our experience with heritage buildings, are of the opinion this entire building requires repointing. In doing this some investigation should first be carried out as to the type of joint which would have been used during the original construction and an assessment of the type of mortar which would be compatible with the stone and the performance of the wall system as a whole.

.2 For a stone building of this kind, bearing in mind the structural support relies on the interface of the variable shaped stones and mortar, we consider it to be in relatively good condition. The fact that settlement has occurred is inevitable with buildings of this kind especially since in all probability the footing consists only of a wider field stone base and not concrete. What appears to be the top of the wider footing under the basement walls could be seen in various locations. As well, from the descriptions provided as to how the vault floor had maintained an elevation along the centre line and dropped at the edges, we believe there is little doubt that the entire perimeter of the building both the front section and the vault area has settled.

.3 Whilst the separation between the vault and the main two storey building on the east wall is very apparent and in all probability will continue to move over the years, we again do not believe this to be of structural significance. After initial repointing and perhaps some reinforcement using either carbon fibre or fibreglass rods in certain of the joints at the worst locations, there will still be a need to have a regular maintenance program as for any other building.

3. DISCUSSION (CONTINUED)

- .4 Insofar as the northeast and northwest corners of the vault are concerned, again as of this time the result of foundation movement appears to be related to mortar joints and not to "breaking" of the stone itself, or to significant differential movement.
- .5 The fire escape originally serving the second floor should either be removed to prevent accidents to trespassers, or investigated and stabilized against the time when the second floor could perhaps be re-used.
- .6 The north face of the office building which has been parged at some time prevents a good examination of the stone and perhaps problems which are not evident from the present visible conditions. However, at this time we believe this entire wall should be stripped back to the stone and again the joints cleaned out and properly prepared for mortar repointing.
- .7 Insofar as the tension tie rods which have been installed at the second floor to deal with wall movement are concerned, we are of the opinion this requires investigation beyond the scope of this initial report. In order to do this we believe all of these walls should be stripped back to bare stone, which if the second floor area was to be returned to a usable condition would be a mandatory requirement anyway. Based on our experience with heritage buildings and probably the most similar to this condition would be the Big House at Lower Fort Garry with which we were associated for several years, I believe these walls can be either rebuilt using the original stone. At this time such would be my primary recommendation, or by further investigation, partial rebuilding and "pinning" the walls together using epoxy anchored stainless steel, or carbon fibre rods would be a reasonable and not particularly expensive solution if the wall has in fact delaminated. What we could not determine at this time from any of the exposed areas, is whether or not the walls are of "solid" stone construction which is what I would anticipate, or in fact consists of two faces with a rubblestone fill which was also very common for thick walls of this type at the time this building was constructed. Again, we suggest if restoration of this building is undertaken, more detailed preliminary work will be necessary in order to establish parameters for the actual remediation.

**3. DISCUSSION (CONTINUED)**

- .8 There is no question that the building has moved in various ways due to the type of construction, the age and to some degree the absence of heating in the case of the second floor. Until the walls are stripped at the second floor level in preparation for new finish materials, the two or three more significant areas of movement both on the floor and the one particular door (photo 21) cannot properly be assessed in terms of implications. However, if it is accepted that the building will move and continue to do so for the next 50 - 100 years, then regular maintenance after initial reconstruction would obviously be a parameter to be maintained.
- .9 We did not attempt to access the roof, but it is the writer's understanding from conversations with Vic Repel, that the roof is considered to be in good condition. However, sight unseen, but on the basis of past experience, we suggest that a roofing inspection should be undertaken by a company such as Aegises Consultants, with particular attention to any penetrations and particularly to the parapet walls. One of the primary causes for wall deterioration in buildings of this kind is the moisture penetration from the roof into the wall system and thence percolating down through the soft lime mortar. Again, with sight unseen, we suggest it may be desirable and in fact necessary to modify the parapets as part of the wall restoration program in order to maintain a watertight condition compatible with the actual roofing.
- .10 With respect to the two basements and the high humidity as a consequence of moisture penetration through the walls and through the floor, we believe this could be alleviated in large part by the use of dehumidifiers with humidistats controlling same. This should be done in combination with an air handling system that would in fact move air through the basement and assist in drying them out and establishing a better humidity condition. It was interesting to note that the sample wood joists which were tested with a pocketknife blade all appeared to be relatively good and I found no significant rot where they bear into the walls. However, when the wood posts were checked there is no doubt that some rot exists in the bottom of these posts; this condition can either be repaired with modern materials and/or replaced with custom heavy duty teleposts. This of course applies only to the front two storey section under the Land Titles since the vault is of concrete construction.

**3. DISCUSSION (CONTINUED)**

- .11 If there is any interest in restoring at least in part the interior of the second floor of this building, then much of the original trim could be retained and refinished. Whilst all of the window system of course need replacement with changes to accommodate interior insulation and vapour barrier systems, other aspects could readily be reworked, or re-installed. As well, if a true heritage restoration of the second floor was required, we believe that certain materials could be re-milled by specialist carpenter companies in the city of Winnipeg.
- .12 The present second floor egress would obviously require changes not only to the present staircase, but provision of either a second exit stair, or restoration of the external fire escape which could possibly be approved on a "grandfather" clause basis.
- .13 Whilst we confirm that there is some "buckling" of the second floor, bearing in mind that to the best of our knowledge the majority of the framing system is of concrete, at the present time I suspect the floor buckling may be due to the unheated condition causing moisture absorption and deterioration of the sleeper system and/or the flooring itself. It is certainly not uncommon in heritage buildings of this kind which have been left unattended to find that the increase in humidity has caused sufficient swelling as to buckle the floor off the support system be it joist or sleepers in the same manner as exists in this case. Whether or not it would be necessary to completely remove the flooring system of the second level would depend on a further and more detailed investigation. At the present time however we believe that a combination of repairs and/or retaining the original system perhaps as a finish to both areas with a self-levelling gypsum or light weight concrete topping could be an acceptable solution.
- .14 In view of the amount of moisture penetrating the exterior basement walls the most desirable improvement would be to excavate around those portions of the building which were accessible, to clean out and repoint the joints, followed by application of a membrane waterproofing system. Finally a new drain tile system and stone backfill

**3. DISCUSSION (CONTINUED)**

could be utilized to improve the drainage against the face of the wall and minimize future moisture problems from that source. In the case of the two walls that front onto town sidewalks the optimum solution from a cost point of view would likely be to clean out all mortar joints, repoint these with a material such as "Thorite" and then apply a skim coat of either "Thorseal", or some other product which would aid in water resistance. Insofar as the basement slab is concerned as long as this area remains storage, etc. which based on the limited head room would undoubtedly be the case, then maintaining a dry condition by controlling humidity and providing sufficient air movement is all that would be required.

**4. CONCLUSIONS**

- .1 In our opinion the ultimate "fate" of this building will depend on management decisions to either retain and upgrade it either as a heritage building and/or as usable rental space, alternatively for other reasons to allow it to continue to deteriorate until a point has been reached where demolition is the only reasonable solution. This latter option has been postulated in past reports, but is not subscribed to as an option by the writer. We believe this is a very interesting and desirable heritage building, contributes considerably to the downtown area of Morden and as an example of field stone construction should if at all possible be retained with full heritage restoration.
- .2 Unless a decision is made to remove this building, there is no doubt that total repointing of the exterior must occur at the earliest possible date if more rapid deterioration of the wall system and thence the interior is not to occur. We suggest in view of the time of the year that the repointing should certainly form part of the work for the construction season of 2002. Ideally however if a political decision was made to retain the building and upgrade it, then the repointing should obviously be done in conjunction with either the installation of new window systems of a matching heritage style, or other remedial works with the repointing being the last item done after all other movement, etc. has been completed.


4. CONCLUSIONS (CONTINUED)

- .3 Whilst considerable concern has apparently been expressed over the years regarding the buckling, "bowing", or separation of the second floor walls towards the northwest corner of the office area, at this time we do not believe this to be especially significant from a structural viewpoint and easily remedied if the will is there to retain this building. As indicated in the earlier sections of this report, further investigation including dismantling some of that wall would be a pre-requisite to a final decision on remediation. Any such remediation would obviously create a condition where the tension ties are not required and bearing in mind their present condition I question whether or not they are in fact contributing anything to the stability of the wall.
- .4 As a general comment regarding the structural adequacy of this building, based on my experience with numerous heritage buildings and restoration, at this time I do not consider the building to be structurally dangerous, or to be in a condition which would preclude upgrading as already discussed in various areas of this report. In making this judgement call we suggest that the authorities responsible must acknowledge that older buildings of this kind whether they be in the core area of Winnipeg, or in rural communities do require regular maintenance. All buildings on spread footing type foundations are susceptible to movement, which in turn are also susceptible to changes in moisture contents and other soil conditions. In our opinion were this building to be restored properly and all necessary work undertaken as an overall upgrading, then with on going maintenance I see no reason why this building should not be standing 50 to 100 years from now.
- .5 Finally as a conclusion based on our experience with heritage buildings, we are of the opinion it would be most unfortunate were this building allowed to degenerate any further and/or be demolished.
- .6 In view of the numerous alternatives which could be considered with respect to maintaining, or restoring this building, even very preliminary budgets are very difficult to assess since we have no knowledge as to how the Province might elect to use the

4. CONCLUSIONS (CONTINUED)

second floor space. Obviously such things as handicap access, internal reworking of toilet facilities, etc. plus mechanical and electrical systems would be part of the overall upgrade. Until these parameters can be established or were established budgets can obviously not be determined.

Respectfully submitted,




A. F. Eshmade, P. Eng.

AFE/jr




**APPENDIX I: PHOTOGRAPHS**






1. VIEW FROM SOUTHEAST.



2. DECORATIVE CORNICE AT SOUTHEAST CORNER.




3. EAST WALL SEPARATION BETWEEN "VAULT" AND FRONT SECTION.




TYPICAL SEPARATION CRACK SHOWING POOR PREVIOUS MORTAR REPAIR.

4.



5. UPPER WALL AT JUNCTION OF "VAULT" AND FRONT SECTION.




6. TYPICAL MORTAR REPOINTING DELAMINATION FROM STONE AND OLD MORTAR JOINT.




7. UPPER NORTHEAST CORNER - NORTH FACE.




8. LOWER WALL AT NORTHEAST CORNER - NORTH FACE.



9. NORTHWEST CORNER OF "VAULT"  
AT SECOND FLOOR FIRE ESCAPE  
AND MORTAR DETERIORATION.



LOWER NORTHWEST CORNER  
AT "VAULT" - NORTH FACE. 10.



11. WEST SIDE OF NORTHWEST CORNER OF "VAULT". NOTE PREVIOUS MORTAR REPAIRS TO STONE SEPARATION.



NORTH FACE OF WEST OFFICE AREA. NOTE PAST ATTEMPTS TO CORRECT STONE WALL CONDITION BY USE OF CEMENT PARGING.


12.

13. NORTHWEST UPPER CORNER IN PHOTO 12 - NORTH FACE.




LOWER NORTHWEST  
CORNER - NORTH FACE.

14.






15. ROD "TENSION" TIES AT SECOND FLOOR LOOKING EAST TOWARDS CORRIDOR WALL.



16. CLOSE UP OF "TENSION" TIE.







17. TENSION TIES AT NORTHWEST CORNER.




18. SECOND FLOOR BOARDS, SLEEPERS AND ASH FILL AS "ACOUSTIC" TREATMENT.




19. SAMPLE SECOND FLOOR LEAKAGE AND PLASTER DAMAGE. TA BRIT MOE V



20. SECOND FLOOR PLASTER DAMAGE - NOTE DOOR TRIM IS STILL "SQUARE".




21. SECOND FLOOR DOOR TO CORRIDOR. ONLY DOOR AND FRAME SHOWING EXCESSIVE MOVEMENT.




22. MAIN FLOOR CEILING AND WALL SEPARATION AT TOP OF BASEMENT STAIRS ADJACENT TO "VAULT".

22.



23. CEILING AND CONCRETE COLUMN  
CRACKING AT NORTH END SPAN  
OF "VAULT" - WEST FACE.




CEILING AND CONCRETE  
COLUMN CRACKING AT NORTH  
END SPAN OF "VAULT" - EAST  
FACE.


24.



25. MAIN FLOOR BEAM IN VAULT BASEMENT UNDER PHOTO 23 - WEST FACE.



26. MAIN FLOOR BEAM IN VAULT BASEMENT UNDER PHOTO 23 - EAST FACE.




27. MAIN FLOOR "SHORING" IN CORNER OF SMALL BASEMENT.



28. CONCRETE COLUMN DETERIORATION AT BASEMENT FLOOR UNDER "VAULT" - SOUTH END.




29. TYPICAL "FIELD STONE" BASEMENT WALL WITH DETERIORATED MORTAR JOINTS.



30. TYPICAL BASEMENT WALL SHOWING MORTAR FALLEN FROM JOINTS.



31. TYPICAL BASEMENT WALL SHOWING MORTAR FALLEN FROM JOINTS.



32. SOUTH ELEVATION.





**City of Morden**  
100-195 Stephen Street  
Morden, Manitoba, R6M 1V3  
Telephone: 204-822-4434 | Fax: 204-822-6494

---

**SCHEDULE E**  
**HAZARDOUS MATERIAL REPORT**

January 23, 2017

# Asbestos-Containing Materials Survey



Morden Land Titles Building, Morden, Manitoba

**Submitted to:**

Stewart McKenzie  
Accommodation Services Division  
Operations Branch  
1129 Queens Avenue  
Brandon, MB R7A 1L9



TESSERACT  
ENVIRONMENTAL CONSULTING INC.

Asbestos-Containing Materials



## TABLE OF CONTENTS

1.0	EXECUTIVE SUMMARY .....	2
2.0	INTRODUCTION .....	2
2.1	Background Information .....	2
3.0	SCOPE OF WORK .....	2
4.0	REGULATIONS AND GUIDELINES .....	3
5.0	METHODOLOGY .....	3
5.1	Asbestos-Containing Materials .....	3
6.0	ENVIRONMENTAL SERVICES .....	4
7.0	RESULTS AND OBSERVATIONS .....	4
8.0	RECOMMENDATIONS .....	6
8.1	Asbestos-Containing Materials .....	6
9.0	LIMITATIONS .....	6
10.0	CLOSURE .....	7

**Document Attachments:**

- Appendix A – Laboratory Certificate of Analysis – Asbestos**
- Appendix B – Photo Index**
- Appendix C – Floor Plans**

## 1.0 EXECUTIVE SUMMARY

A comprehensive investigation for asbestos-containing materials has been undertaken to provide a complete understanding of remedial actions that may be required. Before renovations or maintenance can take place, it is required under Manitoba Regulation 217/2006, Parts 36 and 37 that all asbestos-containing materials that will be affected by these activities be removed or managed in a manner that does not create a risk to the health and safety of any person.

Several styles of flooring were observed throughout the Site. Only the 9"x9" vinyl floor tiles found in the basement #2 washroom were confirmed to be asbestos-containing.

Drywall with asbestos-containing joint compound was observed on walls throughout the 2<sup>nd</sup> level of the Site building. All drywall with joint compound observed on the 2<sup>nd</sup> level was either confirmed as asbestos-containing, or was visually indistinguishable from the asbestos-containing materials. As such, all joint compound finished walls and ceilings should be treated as asbestos-containing, and be removed under appropriate safety precautions.

## 2.0 INTRODUCTION

Tesseract Environmental Consulting Inc. (TEC) was retained by the Accommodation Services Division (ASD) of Manitoba Finance to complete an Asbestos-Containing Materials Survey within the ASD building #100313 – Morden Land Titles Office, located at 351 Stephen Street in Morden, Manitoba (the Site). The assessment was conducted on December 16, 2016 by Mr. Jeff Wright of TEC. Mr. Ken Saunders (the Site Representative) arranged access to the Site during the investigation, and has provided TEC with additional Site details and information.

### 2.1 Background Information

Prior to and during the investigation, limited previous sampling information was available for review.

The Site Survey was performed with the objective of identifying additional asbestos-containing materials that may require abatement prior to renovating or demolishing any areas of the property, and in response to concerns raised by Site personnel about damaged materials on Site. TEC understands that ASD will provide this report to contractors or staff who will be performing any maintenance, demolition, renovations, or alterations at the Site. This report has been compiled to assist ASD in meeting the requirements of Section 4 – Duties of Employers, of Chapter W210 10/02 The Workplace Safety and Health Act as amended, Manitoba Regulation 217/2006 Part 37, and the Workplace Safety and Health documents titled *Guideline for an Asbestos Operations and Maintenance Program* and *Guideline for Working with Asbestos*.

## 3.0 SCOPE OF WORK

The Scope of Work for this project was limited to the following:

- Conduct a room-by-room visual assessment of the Site to determine the location and condition of potentially asbestos-containing materials present at the Site.
- Conduct representative bulk sampling of materials suspected to contain asbestos to supplement observations at the Site.

- Submit the bulk samples collected to an accredited lab, under chain of custody protocol, for analysis.
- Provide a report outlining our findings, and provide recommendations regarding the removal of the identified substances in accordance with planned remediation activities at the Site building.

## 4.0 REGULATIONS AND GUIDELINES

The regulations, guidelines and standards relevant to hazardous building materials include the Manitoba Workplace Health and Safety Regulation, July 31, 2015 (M.R. 217/2006), Manitoba Workplace Safety and Health Division's Guideline entitled *Guideline for Working with Asbestos* (March 2008), and the Manitoba Dangerous Goods Handling and Transportation Act.

Part 36 of M.R. 217/2006 prescribes airborne occupational exposure limits to chemical and biological substances based on Threshold Limit Values (TLV's) established by the American Conference of Governmental Industrial Hygienists (ACGIH). The TLVs for a contaminant represents conditions to which it is believed that nearly all workers may be exposed, day after day, over a working lifetime, without adverse health effects.

Part 37 of M.R. 217/2006 prescribes the overall requirements of a building owner or operator with respect to asbestos-containing materials in the workplace, as well as responsibilities prior to renovation or demolition of all or part of a workplace.

Manitoba Regulation 217/2006 defines asbestos substances that may be present within buildings and prescribes requirements regarding their control or removal. Specifically, control or removal of asbestos and other hazardous substances are prescribed under Parts 33 and 37 of M.R. 217/2006, the purpose of which is to limit or prevent occupational exposures prior to any demolition activities. Specific minimum requirements concerning the handling, removal, and disposal of asbestos within a Manitoba workplace are outlined in the document entitled *Guideline for Working with Asbestos* (March 2008). This document clearly outlines monitoring exposure limits, notification and training requirements, personal protection, removal procedures, and general information concerning the safe and effective removal of all asbestos-containing materials (ACM).

## 5.0 METHODOLOGY

The surveyors investigated the Site for suspected asbestos-containing materials. The survey was conducted in such a fashion as to limit damage where possible. As such, the surveyors performed non-intrusive inspection and testing, and assessment of materials in concealed locations (i.e. ceiling spaces or wall cavities) was conducted only where access was readily available.

### 5.1 Asbestos-Containing Materials

The building was visually inspected on a room-by-room basis to confirm the locations of suspect ACM. Where necessary, bulk samples were collected of materials suspected of containing asbestos for confirmation purposes.

Homogeneous materials sampling was utilized during the investigation. Specifically, bulk material sampling was completed on homogeneous materials that are uniform in color, texture, and installation or construction date.

Representative samples of suspected ACM were submitted to Crisp Analytical Laboratories, LLC in Carrollton, Texas, USA for analysis to determine asbestos type and percentage content by polarized light microscopy (PLM), in accordance with U.S. Environmental Protection Act (USEPA) Method EPA/600/R-93/116.

## 6.0 ENVIRONMENTAL SERVICES

TEC collected sixteen suspected asbestos-containing materials from various locations throughout the Site.

Representative samples of suspected ACMs were submitted to the AIHA Accredited Industrial Hygiene Laboratory Crisp Analytical Laboratories, LLC (Crisp) in Carrollton, Texas, USA for analysis to determine asbestos type and percentage content by polarized light microscopy (PLM), in accordance with U.S. Environmental Protection Act (USEPA) Method EPA/600/R-93/116).

## 7.0 RESULTS AND OBSERVATIONS

Select photographs of the Site areas that were sampled for ACM have been included in **Appendix B – Photo Index**. Full laboratory analytical results for all samples have been included in **Appendix A – Laboratory Certificate of Analysis – Asbestos**.

**TABLE 1: Analytical Results of Suspect Asbestos-Containing Materials Collected throughout Morden Land Titles Building**

SAMPLE #	LOCATION	DESCRIPTION	ASBESTOS CONTENT
S-001	Basement#1	Exterior Wall Mortar	None Detected
S-002	Basement#1	Interior Wall Brick	None Detected
S-003	Basement#1	Interior Wall Mortar	None Detected
<b>S-004</b>	<b>Basement#3</b>	<b>Washroom VFT</b>	<b>6% Chrysotile</b>
S-005	Vault	Plaster Ceiling	None Detected
S-006	Vault	Plaster South Wall	None Detected
S-007	Office#1	2x4 Ceiling Tile	None Detected
S-008	Office#1	DJC East Wall	None Detected
S-009	Corridor	DJC S.E Wall	None Detected
S-010	Office#2	DJC West Wall	None Detected
S-011	2 <sup>nd</sup> Floor Corridor adj. Rm 203	Plaster East Wall	None Detected
S-012	2 <sup>nd</sup> Floor Rm 203	Plaster East Wall	None Detected
<b>S-013</b>	<b>2<sup>nd</sup> Floor Rm 203</b>	<b>DJC N.E Wall</b>	<b>2% Chrysotile</b>
<b>S-014</b>	<b>2<sup>nd</sup> Floor Rm 206</b>	<b>DJC West Wall</b>	<b>2% Chrysotile</b>

SAMPLE #	LOCATION	DESCRIPTION	ASBESTOS CONTENT
S-015	2 <sup>nd</sup> Floor Rm 206	Plaster North Wall	None Detected
S-016	2 <sup>nd</sup> Floor Rm 212	Plaster North Wall	None Detected

Based on the results presented in the above table, as well as visual assessments during the Site visit, the following observations can be made with regards to the ACMs found within the Site building:

#### **DRYWALL FINISHES**

Drywall was observed to have been installed on walls throughout multiple areas of the Site. The finishing compound on the 1<sup>st</sup> floor (Samples S-008, S-009, and S-010) was found to be non-asbestos.

Drywall was observed to have been installed on random walls throughout the 2<sup>nd</sup> floor of the Site. The finishing compound on the 2<sup>nd</sup> floor (Samples S-013 and S-014) was found to contain 2% Chrysotile asbestos. This material is friable and rated in good condition. All drywall walls on the 2<sup>nd</sup> floor should be assumed to be asbestos-containing.

#### **PLASTER FINISHES**

Plaster was observed to have been installed on walls and ceilings throughout the Site. The plaster (Samples S-005, S-006, S-011, S-012, S-015 and S-016) was found to be non-asbestos.

#### **CEILING TILES**

A single style of 2x4' pin pattern ceiling tiles were observed throughout the main level of the Site. These ceiling tiles (Sample S-07) were found to have no detectible levels of asbestos.

#### **FLOORING**

One style of 9"x9" tan floor tile was found to contain 6% Chrysotile asbestos (Samples S-004). The floor tile was noted in basement washroom. This material is non-friable and rated in Good condition.

Several styles of vinyl sheet flooring were observed throughout the Site. All Vinyl sheet flooring were found to have been newly installed. All other flooring materials were found to be non-suspect, such as concrete, wood, or carpet.

#### **MECHANICAL INSULATION**

Mechanical line insulation observed on fittings, valves, and tees was non-suspect. It was noted that these materials have been replaced with newer PVC, or have mitered fiberglass corners.

Any hidden mechanical line insulation materials may be ACM, would be considered friable, and their current condition is unknown. All insulated mechanical lines, if uncovered in hidden spaces, should be presumed to contain asbestos until testing can confirm otherwise.

## OTHER

Mortar and brick located on interior walls within were observed throughout basement areas. The mortar and brick (Sample S-001, S-002 and S-003) were found to have no detectible levels of asbestos.

### SPECIAL NOTE: VERMICULITE & OTHER THERMAL WALL INSULATION

The Site survey was conducted in a way as to limit damage to the occupied spaces. As such, wall cavities and other areas were not assessed unless readily available. Block walls, where observed, were not opened or examined. However, it should be noted that Vermiculite is a common insulation found in block walls, and should be considered present until confirmed otherwise just prior to renovations if cinderblock walls are to be demolished.

## 8.0 RECOMMENDATIONS

### 8.1 Asbestos-Containing Materials

Non-friable asbestos-containing floor tiles were found in the basement #2 washroom. This material was in good condition, and can be safely managed in place until renovations or demolition may disturb these items. If removal or repair is required, non-friable floor tiles can be removed following **Type 1** precautions.

Friable asbestos-containing drywall joint compound was found on the 2<sup>nd</sup> floor of the Site. These materials were in good condition, and can be safely managed in place until renovations or demolition may disturb these items. All drywall materials were found to be asbestos-containing, or were visually indistinguishable. If removal or repair is required, less than one square meter of painted drywall is disturbed, and joints can be avoided where possible, these materials can be handled safely under **Type 2** precautions. If more than three hours of work are required, the precautions should be raised to **Type 3**.

## 9.0 LIMITATIONS

This report was prepared for the exclusive use of Manitoba Finance (the "Client"). This report is based on data and information collected during site visit conducted by Tesseract Environmental Consulting (TEC) and is based solely on site conditions encountered at the time of the site visit. Any use which a third party makes of this report, or any reliance on or discussion to be made based on it, are the sole responsibility of the third party.

The work of this project was performed by TEC in accordance with Agreement 4600019263-C, Contract 16\_013 between the Government of Manitoba and Tesseract Environmental Consulting Inc. dated April 7, 2016.

The conclusions and recommendations contained in this report are based upon professional opinions with regard to the subject matter. These opinions are in accordance with currently accepted environmental assessment standards and practices applicable to this location and are subject to the following inherent limitations:

- The data and findings presented in this report are valid as of the date of the investigation. The passage of time, manifestation of latent conditions or occurrence of future events may warrant further exploration at the properties, analysis of the data, and re-evaluation of the findings, observations, and conclusions expressed in this report.
- Additional hazardous building materials not identified in this report may become evident during renovation or demolition activities. Should additional information become available, TEC requests that this information be brought to our attention so that we may re-assess the conclusions presented herein.





- The findings, observations and conclusions expressed by TEC in this report are not, and should not be considered, an opinion concerning compliance of any past or present owner or operator of the Site with any federal, provincial or local laws or regulations.
- TEC will not be responsible for any real or perceived decrease in a property value, its saleability or ability to gain financing through the reporting of information in this report.
- TEC report presents professional opinions and findings of a scientific and technical nature. While attempts were made to relate the data and findings to applicable environmental and occupational health & safety laws and regulations, the report shall not be construed to offer legal opinion or representations as to the requirements of, nor compliance with, environmental and occupational health & safety laws, rules, regulations or policies of federal, provincial, or local government agencies. Any use of this assessment report constitutes acceptance of the limits of TEC liability. TEC liability extends only to its client and not to other parties who may obtain this assessment report. Issues raised by the report should be reviewed by appropriate legal counsel.
- In evaluating the Site conditions, TEC has relied in good faith on information provided by others. We accept no responsibility for any deficiency, misstatements or inaccuracies contained in this report as a result of omissions, misinterpretations or fraudulent acts of the persons involve.
- Any quantities of identified designated substances noted herein are estimated quantities for reporting purposes, and this report is limited in that regard. In the event that designated substances are scheduled to be removed in the future, it is solely the responsibility of the "abatement contractor" to confirm the exact quantities of designated substances to be removed, prior to their removal.

## 10.0 CLOSURE

If you have any questions regarding the information presented in this report, or require further assistance with environmental health and safety issues related to this, or any other Site, please feel free to contact the undersigned at (204) 250 - 0125. Thank you for the opportunity to offer our services.

**TESSERACT ENVIRONMENTAL CONSULTING INC.**

Prepared By:

Jeff Wright

**PROJECT MANAGER**

Reviewed By:

Ann McEachern, BSc.

**OCCUPATIONAL HYGIENE CONSULTANT**

**Attachments:**

**Appendix A – Laboratory Certificate of Analysis – Asbestos**

**Appendix B– Photo Index**

**Appendix C – Floor Plans**




TESSERACT  
ENVIRONMENTAL CONSULTING INC.

## APPENDIX A

### Laboratory Certificate of Analysis - Asbestos

**CA Labs**  
Dedicated to  
Quality

**Crisp Analytical, L.L.C.**  
1929 Old Denton Road  
Carrollton, TX 75006  
Phone 972-242-2754  
Fax 972-242-2798



**CA Labs, L.L.C.**  
12232 Industriplex, Suite 32  
Baton Rouge, LA 70809  
Phone 225-751-5632  
Fax 225-751-5634

## **Materials Characterization - Bulk Asbestos Analysis**

### **Laboratory Analysis Report - Polarized Light**

#### **Tesseract Environmental Consulting**

86 Wheatfield Road  
PO Box 62051 Stn Transcona  
Winnipeg, Mb R2C 5G2

Attn: Jeff Wright

Customer Project: 16-ASD-0002 SPT 36000, Morden Land Titles Buildir  
Reference #: CAL16128426JE Date: 12/27/2016

#### **Analysis and Method**

Summary of polarizing light microscopy (PLM / Stereomicroscopy bulk asbestos analysis) using the methods described in 40CFR Part 763 Appendix E to Subpart E (Interim and EPA 600 / R-93 / 116 (Improved)). The sample is first viewed with the aid of stereomicroscopy. Numerous liquid slide preparations are created for analysis under the polarized microscope where identifications and quantifications are performed. Calibrated liquid refractive oils are used as liquid mounting medium. These oils are used for identification (dispersion staining). A calibrated visual estimation is reported, should any asbestiform mineral be present. Other techniques such as acid washing are used in conjunction with refractive oils for detection of smaller quantities of asbestos. All asbestos percentages are based on calibrated visual estimation traceable to NIST standards for regulated asbestos. Traceability to measurement and calibration is achieved by using known amounts and types of asbestos from standards where analyst and laboratory accuracy are measured.

#### **Discussion**

Vermiculite containing samples may have trace amounts of actinolite-tremolite, where not found by PLM should be analyzed using TEM methods and / or water separation techniques. Suspected actinolite/vermiculite presence will be indicated through the sample comment section of this report.

Fibrous talc containing samples may even contain a related asbestos fiber known as anthophyllite. Under certain conditions the same fiber may actually contain both talc and anthophyllite (a phenomenon called intergrowth). Again, TEM detection methods are recommended. CA Labs PLM report comments will denote suspected amounts of asbestiform anthophyllite with talc, where further analysis is recommended.

Some samples (floor tiles, surfacings, etc.) may contain fibers too small to be detectable by PLM analysis and should be analyzed by TEM bulk protocols.

A "trace asbestos" will be reported if the analyst observes far less than 1% asbestos. CA Labs defines "trace asbestos" as a few fibers detected by the analyst in several preparations and will indicate as such under these circumstances.

#### **Qualifications**

CA Labs is accredited by the National Voluntary Accreditation Program (NVLAP) for selected test methods for airborne fiber analysis (TEM), and for bulk asbestos fiber analysis (PLM). CA Labs is also accredited by AIHA LAP, LLC. in the PLM asbestos field of testing for Industrial Hygiene. All analysts have a college degree in a natural science (geology, biology, or environmental science) or are recognized by a state professional board in one of these disciplines. Extensive in-house training programs are used to augment education background of the analyst. The group leader of polarized light has received supplemental McCrone Research training for asbestos identification. Analysis performed at Crisp Analytical Labs, LLC 1929 Old Denton Road Carrollton, TX 75006

Dallas NVLAP Lab Code 200349-0 TEM/PLM TCEQ# T104704513-15-3 TDH 30-0235  
AIHA LAP, LLC Laboratory #102929

**CA Labs**  
Dedicated to  
Quality

**Crisp Analytical, L.L.C.**  
1929 Old Denton Road  
Carrollton, TX 75006  
Phone 972-242-2754  
Fax 972-242-2798

**CA Labs, L.L.C.**  
12232 Industriplex, Suite 32  
Baton Rouge, LA 70809  
Phone 225-751-5632  
Fax 225-751-5634

Overview of Project Sample Material Containing Asbestos

**Customer Project:** 16-ASD-0002 SPT 36000, Morden Land Titles Buildir **CA Labs Project #:** CAL16128426JE

Sample #	Layer #	Analysts Subsample	Physical Description of	Asbestos type / calibrated visual estimate percent	List of Affected Building Material Types
S004	S004-1		Washroom VFT/ tan floor tile	6% Chrysotile	tan floor tile tan surfaced tan compound white surfaced tan compound
S013	S013-1		DJC/ tan surfaced tan compound	2% Chrysotile	
S014	S014-1		DJC/ white surfaced tan compound	2% Chrysotile	

Dallas NVLAP Lab Code 200349-0 TEM/PLM TCEQ# T104704513-15-3 TDH 30-0235  
AIHA LAP, LLC Laboratory #102929

**Glossary of abbreviations (non-asbestos fibers and non-fibrous minerals):**

ca - carbonate	pe - perlite	fg - fiberglass	pa - palygorskite (clay)
gypsum - gypsum	qu - quartz	mw - mineral wool	
bi - binder		wo - wollastinite	
or - organic		ta - talc	
ma - matrix		sy - synthetic	
mi - mica		ce - cellulose	
ve - vermiculite		br - brucite	
ot - other		ka - kaolin (clay)	

This report relates to the items tested. This report is not to be used by the customer to claim product certification, approval or endorsement by NVLAP, NIST, AIHA LAP, LLC, or any other agency of the federal government. This report may not be reproduced except in full without written permission from CA Labs. These results are submitted pursuant to CA Labs' current terms and sale, condition of sale, including the company's standard warranty and limitations of liability provisions and no responsibility or liability is assumed for the manner in which the results are used or interpreted. Unless notified in writing to return the samples covered by this report, CA Labs will store the samples for a period of ninety (90) days before discarding. A shipping or handling fee may be assessed for the return of any samples.

**CA Labs**  
Dedicated to  
Quality

**Crisp Analytical, L.L.C.**  
1929 Old Denton Road  
Carrollton, TX 75006  
Phone 972-242-2754  
Fax 972-242-2798

**CA Labs, L.L.C.**  
12232 Industriplex, Suite 32  
Baton Rouge, LA 70809  
Phone 225-751-5632  
Fax 225-751-5634

**Polarized Light Asbestiform Materials Characterization**

**Customer Info:** Attn: Jeff Wright  
**Tesseract Environmental Consulting**  
86 Wheatfield Road  
PO Box 62051 Stn Transcona  
Winnipeg, Mb R2C 5G2  
Phone # 204-801-9358  
Fax # 204-480-4348

**Customer Project:**  
16-ASD-0002 SPT 36000,  
Morden Land Titles Building  
**Turnaround Time:**  
5 Days

**CA Labs Project #:**  
CAL16128426JE  
**Date:** 12/27/2016  
**Samples Received:** 12/21/16 12:30pm  
**Date Of Sampling:** None Given  
**Purchase Order #:**

Sample #	Com ment	Layer #	Analysts Subsample	Physical Description of	Homo- geneo us (Y/N)	Asbestos type / calibrated visual estimate percent	Non-asbestos fiber type / percent	Non-fibrous type / percent
S001		1		S001- Exterior Wall Mortar/ gray mortar	y	None Detected	100% qu,ca	
S002		1		S002- Exterior Wall Brick/ tan bricking	y	None Detected	100% qu,ot	
S003		1		S003- Exterior Wall Mortar/ gray mortar	y	None Detected	100% qu,ca	
S004		1		S004- Washroom VFT/ tan floor tile	y	6% Chrysotile	94% qu,ca	
		2		S004- black mastic	y	None Detected	100% qu,bi	
S005		1		S005- Plaster Ceiling/ white surfaced white finishing plaster	n	None Detected	100% qu,bi,ca	
S006		1		S006- Plaster South Wall/ white surfaced white finishing plaster	n	None Detected	100% qu,bi,ca	

Dallas NVLAP Lab Code 200349-0 TEM/PLM TCEQ# T104704513-15-3 TDH 30-0235

**AIHA LAP, LLC Laboratory #102929**


Analysis Method: Interim (40CFR Part 763 Appendix E to Subpart E) / Improved (EPA-600 / R-93/116) All sampled recieved in good condition unless noted.


Preparation Method: HCL acid washing for carbonate based samples, chemical reduction for organically bound components, oil immersion for

identification of asbestos types by dispersion attaining / becke line method.

ca - carbonate	mi - mica	fg - fiberglass	ce - cellulose
gypsum - gypsum	ve - vermiculite	mw - mineral wool	br - brucite
bi - binder	ot - other	wo - wollastinite	ka - kaolin (clay)
or - organic	pe - perlite	ta - talc	pa - palygorskite (clay)
ma - matrix	qu - quartz	sy - synthetic	

Approved Signatories:

  
Stanley Massett  
Analyst

  
QAC  
Leslie Crisp, P.G.

Technical Manager  
Chad Lytle

1. Fire Damage significant fiber damage - reported percentages reflect unaltered fibers
2. Fire Damage no significant fiber damage effecting fibrous percentages
3. Actinolite in association with Vermiculite
4. Layer not analyzed - attached to previous positive layer and contamination is suspected
5. Not enough sample to analyze

6. Anthophyllite in association with Fibrous Talc
7. Contamination suspected from other building materials
8. Favorable scenario for water separation on vermiculite for possible analysis by another method
9. < 1% Result point counted positive
10. TEM analysis suggested

**CA Labs**  
Dedicated to  
Quality

**Crisp Analytical, L.L.C.**  
1929 Old Denton Road  
Carrollton, TX 75006  
Phone 972-242-2754  
Fax 972-242-2798

**CA Labs, L.L.C.**  
12232 Industriplex, Suite 32  
Baton Rouge, LA 70809  
Phone 225-751-5632  
Fax 225-751-5634

**Polarized Light Asbestiform Materials Characterization**

**Customer Info:** Attn: Jeff Wright  
**Tesseract Environmental Consulting**  
86 Wheatfield Road  
PO Box 62051 Stn Transcona  
Winnipeg, Mb R2C 5G2  
Phone # 204-801-9358  
Fax # 204-480-4348

**Customer Project:**  
16-ASD-0002 SPT 36000,  
Morden Land Tiles Building  
**Turnaround Time:**  
5 Days

**CA Labs Project #:**  
CAL16128426JE  
**Date:** 12/27/2016  
**Samples Received:** 12/21/16 12:30pm  
**Date Of Sampling:** None Given  
**Purchase Order #:**

Sample #	Com ment	Layer #	Analysts Subsample	Physical Description of	Homo- geneo us (Y/N)	Asbestos type / calibrated visual estimate percent	Non-asbestos fiber type / percent	Non-fibrous type / percent
S007		1		S007- 2x4 Ceiling Tile/ white surfacing	y	None Detected		100% qu,bi
		2		S007- gray ceiling tile	y	None Detected	20% fg 60% ce	20% qu,pe,ma
S008		1		S008- DJC/ white compound	y	None Detected		100% qu,pe,ca
S009		1		S009- DJC/ tan surfaced white compound	n	None Detected		100% qu,pe,bi,ca
S010		1		S010- DJC/ tan surfaced white compound	n	None Detected		100% qu,pe,bi,ca
S011		1		S011- Plaster/ tan surfaced white finishing plaster	n	None Detected		100% qu,bi,ca
		2		S011- gray plaster	y	None Detected		100% qu,ca

Dallas NVLAP Lab Code 200349-0 TEM/PLM TCEQ# T104704513-15-3 TDH 30-0235

**AIHA LAP, LLC Laboratory #102929**

Analysis Method: Interim (40CFR Part 763 Appendix E to Subpart E) / Improved (EPA-600 / R-93/116) All sampled recieved in good condition unless noted.

Preparation Method: HCL acid washing for carbonate based samples, chemical reduction for organically bound components, oil immersion for

identification of asbestos types by dispersion attaining / becke line method.

ca - carbonate	mi - mica	fg - fiberglass	ce - cellulose
gypsum - gypsum	ve - vermiculite	mw - mineral wool	br - brucite
bi - binder	ot - other	wa - wollastinite	ka - kaolin (clay)
or - organic	pe - perlite	ta - talc	pa - palygorskite (clay)
ma - matrix	qu - quartz	sy - synthetic	

Approved Signatories:



Stanley Massett  
Analyst



QAC  
Leslie Crisp, P.G.

Technical Manager  
Chad Lytle

1. Fire Damage significant fiber damage - reported percentages reflect unaltered fibers
2. Fire Damage no significant fiber damages effecting fibrous percentages
3. Actinolite in association with Vermiculite
4. Layer not analyzed - attached to previous positive layer and contamination is suspected
5. Not enough sample to analyze

6. Anthophyllite in association with Fibrous Talc
7. Contamination suspected from other building materials
8. Favorable scenario for water separation on vermiculite for possible analysis by another method
9. < 1% Result point counted positive
10. TEM analysis suggested

**CA Labs**  
Dedicated to  
Quality

**Crisp Analytical, L.L.C.**  
1929 Old Denton Road  
Carrollton, TX 75006  
Phone 972-242-2754  
Fax 972-242-2798

**CA Labs, L.L.C.**  
12232 Industripex, Suite 32  
Baton Rouge, LA 70809  
Phone 225-751-5632  
Fax 225-751-5634

## Polarized Light Asbestiform Materials Characterization

**Customer Info:** Attn: Jeff Wright  
**Tesseract Environmental Consulting**  
86 Wheatfield Road  
PO Box 62051 Stn Transcona  
Winnipeg, Mb R2C 5G2  
Phone # 204-801-9358  
Fax # 204-480-4348

**Customer Project:**  
16-ASD-0002 SPT 36000,  
Morden Land Titles Building  
**Turnaround Time:**  
5 Days

**CA Labs Project #:**  
CAL16128426JE  
**Date:** 12/27/2016  
**Samples Received:** 12/21/16 12:30pm  
**Date Of Sampling:** None Given  
**Purchase Order #:**

Sample #	Com ment	Layer #	Analysts Subsample	Physical Description of	Homo- geneo us (Y/N)	Asbestos type / calibrated visual estimate percent	Non-asbestos fiber type / percent	Non-fibrous type / percent
S012		1		S012- <b>Plaster/ white surfaced white finishing plaster</b>	n	<b>None Detected</b>		100% qu,bi,ca
		2		S012- <b>gray plaster</b>	y	<b>None Detected</b>		100% qu,ca
S013		1		S013- <b>DJC/ tan surfaced tan compound</b>	n	<b>2% Chrysotile</b>		98% qu,mi,bi,ca
S014		1		S014- <b>DJC/ white surfaced tan compound</b>	n	<b>2% Chrysotile</b>		98% qu,mi,bi,ca
S015		1		S015- <b>Plaster/ tan surfaced white finishing plaster</b>	n	<b>None Detected</b>		100% qu,bi,ca
		2		S015- <b>gray plaster</b>	y	<b>None Detected</b>		100% qu,ca
S016		1		S016- <b>Plaster/ tan surfaced white finishing plaster</b>	n	<b>None Detected</b>		100% qu,bi,ca

Dallas NVLAP Lab Code 200349-0 TEM/PLM TCEQ# T104704513-15-3 TDH 30-0235

### AIHA LAP, LLC Laboratory #102929

Analysis Method: Interim (40CFR Part 763 Appendix E to Subpart E) / Improved (EPA-600 / R-93/116) All sampled recieved in good condition unless noted.

Preparation Method: HCL acid washing for carbonate based samples, chemical reduction for organically bound components, oil immersion for identification of asbestos types by dispersion attaining / becke line method.

ca - carbonate	mi - mica	fg - fiberglass	ce - cellulose
gypsum - gypsum	ve - vermiculite	mw - mineral wool	br - brucite
bi - binder	ot - other	wo - wollastinite	ka - kaolin (clay)
or - organic	pe - perlite	ta - talc	pa - palygorskite (clay)
ma - matrix	qu - quartz	sy - synthetic	

Approved Signatories:



Stanley Massett  
Analyst



QAC  
Leslie Crisp, P.G.

Technical Manager  
Chad Lytle

1. Fire Damage significant fiber damage - reported percentages reflect unaltered fibers
2. Fire Damage no significant fiber damages effecting fibrous percentages
3. Actinolite in association with Vermiculite
4. Layer not analyzed - attached to previous positive layer and contamination is suspected
5. Not enough sample to analyze

6. Anthophyllite in association with Fibrous Talc
7. Contamination suspected from other building materials
8. Favorable scenario for water separation on vermiculite for possible analysis by another method
9. < 1% Result point counted positive
10. TEM analysis suggested

**CA Labs**  
Dedicated to  
Quality

**Crisp Analytical, L.L.C.**  
1929 Old Denton Road  
Carrollton, TX 75006  
Phone 972-242-2754  
Fax 972-242-2798

**CA Labs, L.L.C.**  
12232 Industriplex, Suite 32  
Baton Rouge, LA 70809  
Phone 225-751-5632  
Fax 225-751-5634

**Polarized Light Asbestiform Materials Characterization**

**Customer Info:** Attn: Jeff Wright  
**Tesseract Environmental Consulting**  
86 Wheatfield Road  
PO Box 62051 Stn Transcona  
Winnipeg, Mb R2C 5G2  
Phone # 204-801-9358  
Fax # 204-480-4348

**Customer Project:**  
16-ASD-0002 SPT 36000,  
Morden Land Titles Building  
**Turnaround Time:**  
5 Days

**CA Labs Project #:**  
CAL16128426JE  
**Date:** 12/27/2016  
**Samples Received:** 12/21/16 12:30pm  
**Date Of Sampling:** None Given  
**Purchase Order #:**

Sample #	Com ment	Layer #	Analysts Subsample	Physical Description of	Homo- geneo us (Y/N)	Asbestos type / calibrated visual estimate percent	Non-asbestos fiber type / percent	Non-fibrous type / percent
S016- 2				gray plaster	y	None Detected		100% qu,ca

Dallas NVLAP Lab Code 200349-0 TEM/PLM TCEQ# T104704513-15-3 TDH 30-0235

**AIHA LAP, LLC Laboratory #102929**

Analysis Method: Interim (40CFR Part 763 Appendix E to Subpart E) / Improved (EPA-600 / R-93/116) All sampled recieved in good condition unless noted.

Preparation Method: HCL acid washing for carbonate based samples, chemical reduction for organically bound components, oil immersion for

identification of asbestos types by dispersion attaining / becke line method.

ca - carbonate	mi - mica	fg - fiberglass	ce - cellulose
gypsum - gypsum	ve - vermiculite	mw - mineral wool	br - brucite
bi - binder	ot - other	wo - wollastinite	ka - kaolin (clay)
or - organic	pe - perlite	ta - talc	pa - palygorskite (clay)
ma - matrix	qu - quartz	sy - synthetic	

Approved Signatories:



Stanley Massett  
Analyst



QAC  
Leslie Crisp, P.G.

Technical Manager  
Chad Lytle

1. Fire Damage significant fiber damage - reported percentages reflect unaltered fibers
2. Fire Damage no significant fiber damages effecting fibrous percentages
3. Actinolite in association with Vermiculite
4. Layer not analyzed - attached to previous positive layer and contamination is suspected
5. Not enough sample to analyze

6. Anthophyllite in association with Fibrous Talc
7. Contamination suspected from other building materials
8. Favorable scenario for water separation on vermiculite for possible analysis by another method
9. < 1% Result point counted positive
10. TEM analysis suggested







TESSERACT  
ENVIRONMENTAL CONSULTING INC.

## APPENDIX B

### Photo Index

Appendix B- Photo Index

<p><b>Basement Washroom – Asbestos-Containing 12x12” Grey Streak VFT in Good Condition</b></p>	
<p><b>Non-Asbestos Ceiling Tiles on Main Floor</b></p>	

Appendix B- Photo Index

New Piping, Ducting and  
Boiler



Non-Asbestos Vinyl Sheet  
Flooring in Main Floor  
Washroom






TESSERA CT  
ENVIRONMENTAL CONSULTING INC.

## APPENDIX C

### Floor Plans




Basement Level






**Main Level**



N  
↑  
Second Level





**City of Morden**  
100-195 Stephen Street  
Morden, Manitoba, R6M 1V3  
Telephone: 204-822-4434 | Fax: 204-822-6494

---

**SCHEDULE F**  
**ROOFING REPORT**





April 15, 2021

Stewart McKenzie  
Manitoba Finance Central Services  
1129 Queens Avenue  
Brandon, MB R7A 1L9  
(204) 724-4196

[stewart.mckenzie@gov.mb.ca](mailto:stewart.mckenzie@gov.mb.ca)

**Re: Morden Land Titles Office**

We have completed our inspection at the above address and are pleased to provide you with the following roof condition report and recommendations. This is a 2 story commercial building with 3 roof areas.

**Executive Summary**

Plan Area	Roof System	Condition	Recommendation
Roof A1	Sloped SBS Membrane	Good	Monitor
Roof B1	Sloped SBS Membrane	Good	Monitor
Roof B2	Asphalt and Gravel	Fair to Poor	Replacement Now

**CURRENT ROOF CONDITIONS**

**Roof A1**

- Roof A1 *Figure 1* is a sloped sloped SBS roof system in good condition. This roof was replaced by MJ Roofing in 2020. No work is required at this time.

**Roof B1**

- Roof B1 *Figure 2* is a sloped SBS membrane roof system in good condition. This roof was replaced by MJ Roofing in 2019. No work is required at this time.
- This roof drains to the eavestrough and downpipes along the north wall.

Roof B2

- Roof B2 *Figure 3* is a asphalt and gravel roof system in fair to poor condition.
- Blisters and ridges have developed in the roof membrane, which should be repaired.
- Unused projections are on the roofmat.
- There are open seams on the stripping along the south wall, which should be repaired.
- The stripping along the north, south and west walls has been upgraded with SBS membrane.
- This roof drains to the eavestrough and downpipes along the west side.
- Following provincial safety recommendations, safety rails that meet current CSA standards are recommended to be installed along the outside parapet wall when a roof hatch is within 2 meters of the outside edge of the roof. The hatch requires safety railings along the parapet wall.
- We recommend replacement at this time.



**RECOMMENDATIONS**

**Recommendation #1 - Roof Replacement, Roof B2 (2,306 sq. ft.)**

*Sloped SBS Membrane Roof System*

- Remove existing flashing and save for re-use
- Remove existing roof system down to deck
- Supply and install 1 layer of ½" Smartboard mechanically fastened
- Supply and install 2-ply SBS membrane
- Strip-in all projections and perimeter with 2-ply SBS membrane
- Supply and install 2 new Thaler vent flashings with 3" ABS pipe
- Supply and install new pre-finished metal drip edge
- Supply and install new pre-finished metal termination bar
- Supply and install new roof hatch
- Supply and install engineered approved safety rails around roof hatch
- Remove work related debris

*\*Breakdown:*

<i>Travel</i>	793.10
<i>Foreman - 65 hours @ \$72.10/hour</i>	\$ 4,686.50
<i>Helper - 365 hours @ \$66.95/hour</i>	\$ 24,436.75
<i>Materials</i>	\$ 20,340.50

**Cost..... \$ 50,256.85**

*\*Notes:*

- Remove existing roof hatch curb
- Supply and install new blocking to ensure proper height
- Seal new curb with 2-ply SBS membrane
- Supply and install new roof hatch
- Supply and install engineered approved safety rails around roof hatch
- Damaged decking will be replaced at an additional \$ 5.95 sq. ft. as found
- Upon completion, issue a 5-year RCAM warranty
- Upon completion, issue a 10-year manufacturers warranty



**Recommendation # 2 - General Maintenance, Roof B2**

If not replaced, we recommend the following to attempt to keep Roof B watertight

- Remove 3 unused projections and seal with 2-ply brown SBS membrane, Roof B2 *Figure 4*
- Repair blisters and ridges with cold ply and fabric, Roof B2 (30 lin. ft.)
- Re-seal open seams in stripping with Alsan and granules, Roof B2 *Figure 5*
- Re-secure flashings and caulk as required
- Trim back tree branches, Roof B2
- Remove debris from drains and membrane
- Clean debris from eavestrough

*\*Breakdown:*

Foreman - 16 hours @ \$72.10/hour	\$ 1,153.60
Helper - 16 hours @ \$66.95/hour	\$ 1,071.20
Materials	\$ 391.07

**Cost.....\$ 2,615.87**

\*Prices quoted in this report are guaranteed for 30 days. Approvals to proceed with any work after that time will be subject to a review, and if required, updated pricing.

If you have any further questions, please feel free to contact me.

Yours sincerely,

Eric Lepage  
Account Manager

EL/dy/sd  
Email: [eric@mjroofing.net](mailto:eric@mjroofing.net)

Figure 1 – Overview Roof A1



Figure 2 – Overview Roof B1



Figure 3 – Overview Roof B2




Figure 4 – Remove unused projections and seal, Roof B2



Figure 5 – Re-seal open seams





B1 - 722 sq.ft  
 B2 - 2306 sq.ft  
 2 STOREY

**LEGEND**

- |                  |                       |
|------------------|-----------------------|
| 1) PENTHOUSE     | 14) ROOF HATCH        |
| 2) CHIMNEY       | 15) SCUPPER           |
| 3) AIR CONDITION | 16) PITCH BOXES       |
| 4) SIGN SUPPORT  | 17) GOOSENECK         |
| 5) VENTILATOR    | 18) UNITS ON SLEEPERS |
| 6) VENT PIPE     | 19) SLEEPERS          |
| 7) DRAIN         | 20) MECH CURB         |
| 8) SKYLIGHT      | 21) LADDER            |
| 9) EAVESTROUGH   | 22) OVERFLOW          |
| 10) FIRE WALL    | 23) GRAVITY VENT      |
| 11) ANTENNA/DISH | 24)                   |
| 12) CAPPED CURB  | 25)                   |
| 13) GRAVEL STOP  |                       |

**PROBLEM INDICATOR**

- |          |                |
|----------|----------------|
| PONDING  | LEAK INDICATOR |
| RIDGING  | SPLITS         |
| WET/DAMP | CORE SAMPLE    |

**MISCELLANEOUS**

- |                 |                   |
|-----------------|-------------------|
| A 1ST ELEVATION | EXPANSION JOINT   |
| B 2ND ELEVATION | SBS/UPGRADED      |
| PROPOSED        | COLD PLY/UPGRADED |
| METAL ROOF      | RC 2200/UPGRADED  |
| 4PLY A/G        | SHINGLE ROOF      |
| EPDM            | PROPOSED SAFETY   |
| GAS LINE        | EXISTING SAFETY   |



**MJ ROOFING**  
 908 JARVIS AVENUE, WINNIPEG, MB R2X 0A1  
 TEL: (204) 586-8411 FAX: (204) 589-6114

LOCATION:

**351 STEPHEN ST.**  
 MORDEN, MB

COMPANY:	SCALE:	1"=150'
DATE:	REVISION:	APR 2021
OWNER:	DRAWING #:	mor5074(1).dwg

THIS DRAWING IS THE PROPERTY OF MJ ROOFING & SUPPLY LTD.  
 IT MAY NOT BE REPRODUCED WITHOUT CONSENT.



**City of Morden**  
100-195 Stephen Street  
Morden, Manitoba, R6M 1V3  
Telephone: 204-822-4434 | Fax: 204-822-6494

---

**SCHEDULE G**  
**SEWER LINE REPORT**





5150 Richmond Ave East  
Brandon, MB R7A 7P9

todd@gwvac.com

# Invoice

Invoice To
Manitoba Central Services 1129 Queens Ave Brandon Manitoba R7A 1L9 Operations District 3 Attn: Stewart

Date	Invoice #
2021-08-26	14555

P.O. No.	Terms	W.O No.
2185279	Due on receipt	

Description	Qty	Rate	Amount	Tax
AUG 26/21 ROTO TOOTED AND CAMERA'D SEWER LINES AT LAND TITLES OFFICE. SEWER LINE IN REALLY GOOD SHAPE				
Inspection camera and vehicle per hour	5	89.00	445.00T	P
Operator	5	50.00	250.00T	P
Assistant Operator	5	45.00	225.00T	P

Please pay invoice, no statement will be issued.		<b>Subtotal</b>	\$920.00
GST/HST No. 848694584		<b>Sales Tax Summary</b>	
		PST (1) On Sales@7.0%	64.40
		Total Tax	64.40
		<b>Payments/Credits</b>	\$0.00
		<b>Total</b>	\$984.40



**City of Morden**  
100-195 Stephen Street  
Morden, Manitoba, R6M 1V3  
Telephone: 204-822-4434 | Fax: 204-822-6494

---

**SCHEDULE H**  
**STATUS OF TITLE**



## STATUS OF TITLE

Title Number **3272653/4**  
Title Status **Accepted**  
Client File **8547br City of Morden**



<p><b>1. REGISTERED OWNERS, TENANCY AND LAND DESCRIPTION</b></p> <p>CITY OF MORDEN</p> <p>IS REGISTERED OWNER SUBJECT TO SUCH ENTRIES RECORDED HEREON IN THE FOLLOWING DESCRIBED LAND:</p> <p>LOT 20 BLOCK 27 SS PLAN 863 MLTO EXC ALL MINES AND MINERALS AND OTHER MATTERS AS SET FORTH IN THE CROWN LANDS ACT IN N 1/2 5-3-5 WPM</p> <p>The land in this title is, unless the contrary is expressly declared, deemed to be subject to the reservations and restrictions set out in section 58 of <i>The Real Property Act</i>.</p>
<p><b>2. ACTIVE INSTRUMENTS</b></p> <p>No active instruments</p>
<p><b>3. ADDRESSES FOR SERVICE</b></p> <p>CITY OF MORDEN 100-195 Stephen Street Morden MB R6M 1V3</p>
<p><b>4. TITLE NOTES</b></p> <p>No title notes</p>
<p><b>5. LAND TITLES DISTRICT</b></p> <p>Morden</p>
<p><b>6. DUPLICATE TITLE INFORMATION</b></p> <p>Duplicate not produced</p>
<p><b>7. FROM TITLE NUMBERS</b></p> <p>27626/4                  Part</p>
<p><b>8. REAL PROPERTY APPLICATION / CROWN GRANT NUMBERS</b></p> <p>5539 9357</p>

**9. ORIGINATING INSTRUMENTS**

Instrument Type: **Transfer Of Land**  
Registration Number: **1287960/4**

Registration Date: 2023-11-06  
From/By: H.M. THE KING IN RIGHT OF THE PROVINCE OF MANITOBA  
To: CITY OF MORDEN  
Consideration: \$165,000.00

**10. LAND INDEX**

Lot 20 Block 27 Plan 863  
N 1/2 5-3-5W SS PLAN EXC RES

CERTIFIED TRUE EXTRACT PRODUCED FROM THE LAND TITLES DATA STORAGE  
SYSTEM OF TITLE NUMBER 3272653/4

## STATUS OF TITLE

Title Number **3272650/4**  
Title Status **Accepted**  
Client File **8547br City of Morden**



<p><b>1. REGISTERED OWNERS, TENANCY AND LAND DESCRIPTION</b></p> <p>CITY OF MORDEN</p> <p>IS REGISTERED OWNER SUBJECT TO SUCH ENTRIES RECORDED HEREON IN THE FOLLOWING DESCRIBED LAND:</p> <p>LOT 21 BLOCK 27 SS PLAN 863 MLTO EXC ALL MINES AND MINERALS AND OTHER MATTERS AS SET FORTH IN THE CROWN LANDS ACT IN N 1/2 5-3-5 WPM</p> <p>The land in this title is, unless the contrary is expressly declared, deemed to be subject to the reservations and restrictions set out in section 58 of <i>The Real Property Act</i>.</p>
<p><b>2. ACTIVE INSTRUMENTS</b></p> <p>No active instruments</p>
<p><b>3. ADDRESSES FOR SERVICE</b></p> <p>CITY OF MORDEN 100-195 Stephen Street Morden MB R6M 1V3</p>
<p><b>4. TITLE NOTES</b></p> <p>No title notes</p>
<p><b>5. LAND TITLES DISTRICT</b></p> <p>Morden</p>
<p><b>6. DUPLICATE TITLE INFORMATION</b></p> <p>Duplicate not produced</p>
<p><b>7. FROM TITLE NUMBERS</b></p> <p>20759/4                  Part</p>
<p><b>8. REAL PROPERTY APPLICATION / CROWN GRANT NUMBERS</b></p> <p>5339</p>

**9. ORIGINATING INSTRUMENTS**

Instrument Type: **Transfer Of Land**  
Registration Number: **1287960/4**

Registration Date: 2023-11-06  
From/By: H.M. THE KING IN RIGHT OF THE PROVINCE OF MANITOBA  
To: CITY OF MORDEN  
Consideration: \$165,000.00

**10. LAND INDEX**

Lot 21 Block 27 Plan 863  
N 1/2 5-3-5W SS PLAN EXC RES

CERTIFIED TRUE EXTRACT PRODUCED FROM THE LAND TITLES DATA STORAGE  
SYSTEM OF TITLE NUMBER 3272650/4